

The Sixty Newton Rate Book

Every number the estimating system holds, for line by line review. Generated 2026-09-07.

Data sources

Zoho Books org 719219457, last product update 2026-09-06; 36 quotations imported; TDS defaults; references Tarun, Sep 2026.

Settings in force

Intercompany factor 1.09 on Books costs. Overhead 12% on material. Margin 25% on supply and application prices. VAT 5%, always exclusive.

For the contractor reviewing this

1. Correct any number that is wrong, in the blank column.
2. Cross out work we never do.
3. Add missing work in the margin of the page.
4. Shaded rows marked review are where past quotes and the cost build-up disagree by more than a quarter: check those hardest.
5. Rates marked engine only have no past quotation behind them yet.

Waterproofing

Stage	Product and pack	Coverage and defaults	Material per unit	Labour, history vs engine	Rates	Evidence	Contractor correction
Site survey and moisture test review	labour only	labour only at defaults; no source	0 no material	history 95 (9 quotes: QT-000250, QT-000256, QT-000301) engine 30; history leads	S+A 95/lump App only 30	QT-000250 02 May 2026 85, White Pearl Interiors QT-000256 09 May 2026 90, Mr Istvan Perger, Saadiyat Island QT-000301 24 Aug 2026 45, CATIC	
Substrate preparation (grind, repair, dust extraction) review	labour only	labour only at defaults; no source	0 no material	history 95 (9 quotes: QT-000250, QT-000256, QT-000301) engine 15; history leads	S+A 95/sqm App only 15	QT-000250 02 May 2026 85, White Pearl Interiors QT-000256 09 May 2026 90, Mr Istvan Perger, Saadiyat Island QT-000301 24 Aug 2026 45, CATIC	
Primer review	Mapei Primer SN (epoxy primer) MAPEI, Primer SN A+B 20 KG 20 kg at 538/pack, 26.9/unit	0.4 kg/sqm, waste 5% 1 coat at TDS coverage; tds H	11.3/sqm coverage x pack cost x 1.09 + waste, + overhead 12% = our cost 12.5	history 95 (9 quotes: QT-000250, QT-000256, QT-000301) engine 30; history leads	S+A 95/sqm App only 30	QT-000250 02 May 2026 85, White Pearl Interiors QT-000256 09 May 2026 90, Mr Istvan Perger, Saadiyat Island QT-000301 24 Aug 2026 45, CATIC	
Membrane coat 1 (brush or roller)	Mapei Mapelastc (A+B 32 kg) MAPEI, MAPELASTIC A + B BAGS 32 KG 32 kg at 220/pack, 6.9/unit	1.7 kg/sqm per mm, waste 5% 1 coat at TDS coverage; tds H	24.5/sqm coverage x pack cost x 1.09 + waste, + overhead 12% = our cost 27.5	history 92.5 (8 quotes: QT-000250, QT-000256, QT-000301) engine 30; history leads	S+A 93/sqm App only 30	QT-000250 02 May 2026 85, White Pearl Interiors QT-000256 09 May 2026 90, Mr Istvan Perger, Saadiyat Island QT-000301 24 Aug 2026 45, CATIC	
Reinforcement mesh embed review	Mapei Mapenet 150 (1x50 m) MAPEI, Mapenet 150 roll 1x50mt 50 sqm at 383/pack, 7.7/unit	45 sqm covered per roll (net of lap), waste 0% 1 coat at TDS coverage; tds H	8.5/sqm coverage x pack cost x 1.09 + waste, + overhead 12% = our cost 9.5	history 95 (9 quotes: QT-000250, QT-000256, QT-000301) engine 30; history leads	S+A 95/sqm App only 30	QT-000250 02 May 2026 85, White Pearl Interiors QT-000256 09 May 2026 90, Mr Istvan Perger, Saadiyat Island QT-000301 24 Aug 2026 45, CATIC	
Membrane coat 2	Mapei Mapelastc (A+B 32 kg) MAPEI, MAPELASTIC A + B BAGS 32 KG 32 kg at 220/pack, 6.9/unit	1.7 kg/sqm per mm, waste 5% 1 coat at TDS coverage; tds H	24.5/sqm coverage x pack cost x 1.09 + waste, + overhead 12% = our cost 27.5	history 95 (9 quotes: QT-000250, QT-000256, QT-000301) engine 30; history leads	S+A 95/sqm App only 30	QT-000250 02 May 2026 85, White Pearl Interiors QT-000256 09 May 2026 90, Mr Istvan Perger, Saadiyat Island QT-000301 24 Aug 2026 45, CATIC	
Detailing (corners, penetrations, upstands) review	Mapei Mapeband Easy H130 (30 m) MAPEI, Mapeband Easy H130 roll 30mt 30 lm at 283/pack, 9.4/unit	30 lm per roll, waste 5% 1 coat at TDS coverage; tds H	9.9/lm coverage x pack cost x 1.09 + waste, + overhead 12% = our cost 11	history 95 (9 quotes: QT-000250, QT-000256, QT-000301) engine 30; history leads	S+A 95/lm App only 30	QT-000250 02 May 2026 85, White Pearl Interiors QT-000256 09 May 2026 90, Mr Istvan Perger, Saadiyat Island QT-000301 24 Aug 2026 45, CATIC	
Cure and flood test review	labour only	labour only at defaults; no source	0 no material	history 95 (9 quotes: QT-000250, QT-000256, QT-000301) engine 30; history leads	S+A 95/lump App only 30	QT-000250 02 May 2026 85, White Pearl Interiors QT-000256 09 May 2026 90, Mr Istvan Perger, Saadiyat Island QT-000301 24 Aug 2026 45, CATIC	
Protection screed (e 50 mm) review	labour only	labour only at defaults; no source	0 no material	history 95 (9 quotes: QT-000250, QT-000256, QT-000301) engine 30; history leads	S+A 95/sqm App only 30	QT-000250 02 May 2026 85, White Pearl Interiors QT-000256 09 May 2026 90, Mr Istvan Perger, Saadiyat Island QT-000301 24 Aug 2026 45, CATIC	
Handover IR and documentation review	labour only	labour only at defaults; no source	0 no material	history 95 (9 quotes: QT-000250, QT-000256, QT-000301) engine 30; history leads	S+A 95/lump App only 30	QT-000250 02 May 2026 85, White Pearl Interiors QT-000256 09 May 2026 90, Mr Istvan Perger, Saadiyat Island QT-000301 24 Aug 2026 45, CATIC	

Bitumen WP

Stage	Product and pack	Coverage and defaults	Material per unit	Labour, history vs engine	Rates	Evidence	Contractor correction
Bituminous primer review	labour only	labour only at defaults; no source	0 no material	history 27.5 (4 quotes: QT-000301, QT-000301, QT-000301) engine 37.5; history leads	S+A 28/sqm App only 19	QT-000301 24 Aug 2026 32, CATIC QT-000301 24 Aug 2026 58, CATIC QT-000301 24 Aug 2026 23, CATIC	
Torch-applied membrane layer 1 (4 mm)	labour only	labour only at defaults; no source	0 no material	history 45 (2 quotes: QT-000301, QT-000301) engine 27; history leads	S+A 45/sqm App only 19	QT-000301 24 Aug 2026 32, CATIC QT-000301 24 Aug 2026 58, CATIC	
Membrane layer 2 offset 50% (where 4+4) review	APP modified bitumen 4 mm (1x10 m) GULF SHIELD, APP MODIFIED BITUMEN MEMBRANE 4mm 1 x 10m SHEET - GULF SHIELD 10 sqm at 82/pack, 8.2/unit	8.5 sqm per roll net of laps, waste 3% 1 coat at TDS coverage; tds H	9.9/sqm coverage x pack cost x 1.09 + waste, + overhead 12% = our cost 11	history 27.5 (4 quotes: QT-000301, QT-000301, QT-000301) engine 27; history leads	S+A 28/sqm App only 19	QT-000301 24 Aug 2026 32, CATIC QT-000301 24 Aug 2026 58, CATIC QT-000301 24 Aug 2026 23, CATIC	
Anti-root membrane review	labour only	labour only at defaults; no source	0 no material	history 27.5 (4 quotes: QT-000301, QT-000301, QT-000301) engine 27; history leads	S+A 28/sqm App only 19	QT-000301 24 Aug 2026 32, CATIC QT-000301 24 Aug 2026 58, CATIC QT-000301 24 Aug 2026 23, CATIC	
Geotextile separator 300 gsm review	labour only	labour only at defaults; no source	0 no material	history 27.5 (4 quotes: QT-000301, QT-000301, QT-000301) engine 27; history leads	S+A 28/sqm App only 19	QT-000301 24 Aug 2026 32, CATIC QT-000301 24 Aug 2026 58, CATIC QT-000301 24 Aug 2026 23, CATIC	
Protection board review	Geotextile non-woven (1x50 m) TERRACO NON WOVEN GEOTEXTILE 85GSM (1 X 50MTR) 50 sqm at 281/pack, 5.6/unit	45 sqm per roll, waste 0% 1 coat at TDS coverage; tds M	6.2/sqm coverage x pack cost x 1.09 + waste, + overhead 12% = our cost 7	history 27.5 (4 quotes: QT-000301, QT-000301, QT-000301) engine 27; history leads	S+A 28/sqm App only 19	QT-000301 24 Aug 2026 32, CATIC QT-000301 24 Aug 2026 58, CATIC QT-000301 24 Aug 2026 23, CATIC	
Flood test and IR	labour only	labour only at defaults; no source	0 no material	history 27.5 (4 quotes: QT-000301, QT-000301, QT-000301) engine 0; history leads	S+A 28/lump App only 19	QT-000301 24 Aug 2026 32, CATIC QT-000301 24 Aug 2026 58, CATIC QT-000301 24 Aug 2026 23, CATIC	

Epoxy flooring

Stage	Product and pack	Coverage and defaults	Material per unit	Labour, history vs engine	Rates	Evidence	Contractor correction
Moisture test and survey	labour only	labour only at defaults; no source	0 no material	history 45 (5 quotes: QT-000291, QT-000291, QT-000296 v1) engine 35; history leads	S+A 45/lump App only 35	QT-000291 01 Aug 2026 15, Retail Mall Sharjah QT-000291 01 Aug 2026 130, Retail Mall Sharjah QT-000296 v1 22 Aug 2026 80, Nabd Al Badia	
Shotblast or grind and vacuum review	labour only	labour only at defaults; no source	0 no material	history 15 (2 quotes: QT-000291, QT-000296 / 298) engine 15; history leads	S+A 15/sqm App only 15	QT-000291 01 Aug 2026 15, Retail Mall Sharjah QT-000296 / 298 Aug 2026 15, Nabd Al Badia (Carrefour) / Arabian Furniture (Police HQ)	
Crack and joint repair	labour only	labour only at defaults; no source	0 no material	history 45 (5 quotes: QT-000291, QT-000291, QT-000296 v1) engine 35; history leads	S+A 45/lm App only 35	QT-000291 01 Aug 2026 15, Retail Mall Sharjah QT-000291 01 Aug 2026 130, Retail Mall Sharjah QT-000296 v1 22 Aug 2026 80, Nabd Al Badia	
Primer review	Mapei Primer SN (epoxy primer) MAPEI, Primer SN A+B 20 KG 20 kg at 538/pack, 26.9/unit	0.4 kg/sqm, waste 5% 1 coat at TDS coverage; tds H	11.3/sqm coverage x pack cost x 1.09 + waste, + overhead 12% = our cost 12.5	history 45 (5 quotes: QT-000291, QT-000291, QT-000296 v1) engine 35; history leads	S+A 45/sqm App only 35	QT-000291 01 Aug 2026 15, Retail Mall Sharjah QT-000291 01 Aug 2026 130, Retail Mall Sharjah QT-000296 v1 22 Aug 2026 80, Nabd Al Badia	
Body coat self-levelling 2 to 3 mm review	Mapei Mapefloor I 300 SL (A+B+C 47 kg) MAPEI, Mapefloor I 300 SL ME /A+B+C RAL 6034 bucket 47kg 47 kg at 730/pack, 15.5/unit	1.6 kg/sqm per mm, waste 5% at 2 mm, 1 coat; tds H	52.2/sqm coverage x pack cost x 1.09 + waste, + overhead 12% = our cost 58.5	history 80 (3 quotes: QT-000291, QT-000296 v1, QT-000296 v3) engine 35; history leads	S+A 80/sqm App only 35	QT-000291 01 Aug 2026 130, Retail Mall Sharjah QT-000296 v1 22 Aug 2026 80, Nabd Al Badia QT-000296 v3 22 Aug 2026 45, Nabd Al Badia	
Broadcast quartz or flake	Quartz sand 0.5 mm (25 kg) MAPEI, Quartz 0.5mm bag 25kg 25 kg at 41/pack, 1.6/unit	3 kg/sqm, waste 0% 1 coat at TDS coverage; tds M	4.9/sqm coverage x pack cost x 1.09 + waste, + overhead 12% = our cost 5.5	history 45 (5 quotes: QT-000291, QT-000291, QT-000296 v1) engine 35; history leads	S+A 45/sqm App only 35	QT-000291 01 Aug 2026 15, Retail Mall Sharjah QT-000291 01 Aug 2026 130, Retail Mall Sharjah QT-000296 v1 22 Aug 2026 80, Nabd Al Badia	
Top sealer × 2 coats (UV-stable PU)	labour only	labour only at defaults; no source	0 no material	history 45 (5 quotes: QT-000291, QT-000291, QT-000296 v1) engine 35; history leads	S+A 45/sqm App only 35	QT-000291 01 Aug 2026 15, Retail Mall Sharjah QT-000291 01 Aug 2026 130, Retail Mall Sharjah QT-000296 v1 22 Aug 2026 80, Nabd Al Badia	
PU-cement heavy duty 6 to 9 mm (F&B, cold rooms) review	Mapei Mapefloor CPU/MF (A+B+C 28.32 kg) MAPEI, MAPEFLOOR CPU+/MF A+B+C 28.32 KG 28.32 kg at 442/pack, 15.6/unit	2 kg/sqm per mm, waste 5% at 2 mm, 1 coat; tds M	65.5/sqm coverage x pack cost x 1.09 + waste, + overhead 12% = our cost 73.5	history 45 (5 quotes: QT-000291, QT-000291, QT-000296 v1) engine 35; history leads	S+A 45/sqm App only 35	QT-000291 01 Aug 2026 15, Retail Mall Sharjah QT-000291 01 Aug 2026 130, Retail Mall Sharjah QT-000296 v1 22 Aug 2026 80, Nabd Al Badia	
Coving	labour only	labour only at defaults; no source	0 no material	history 45 (5 quotes: QT-000291, QT-000291, QT-000296 v1) engine 35; history leads	S+A 45/lm App only 35	QT-000291 01 Aug 2026 15, Retail Mall Sharjah QT-000291 01 Aug 2026 130, Retail Mall Sharjah QT-000296 v1 22 Aug 2026 80, Nabd Al Badia	

Sports and TNS coatings	labour only	labour only at defaults; no source	0 no material	history 45 (5 quotes: QT-000291, QT-000291, QT-000296 v1) engine 35; history leads	S+A 45/sqm App only 35	QT-000291 01 Aug 2026 15, Retail Mall Sharjah QT-000291 01 Aug 2026 130, Retail Mall Sharjah QT-000296 v1 22 Aug 2026 80, Nabd Al Badia
Cure schedule	labour only	labour only at defaults; no source	0 no material	history 45 (5 quotes: QT-000291, QT-000291, QT-000296 v1) engine 35; history leads	S+A 45/sqm App only 35	QT-000291 01 Aug 2026 15, Retail Mall Sharjah QT-000291 01 Aug 2026 130, Retail Mall Sharjah QT-000296 v1 22 Aug 2026 80, Nabd Al Badia

SL & screed

Stage	Product and pack	Coverage and defaults	Material per unit	Labour, history vs engine	Rates	Evidence	Contractor correction
Edge banding and dams review	labour only	labour only at defaults; no source	0 no material	history 120 (13 quotes: QT-000250, QT-000304, QT-000184) engine 37.5; history leads	S+A 120/lm App only 80	QT-000250 02 May 2026 165, White Pearl Interiors QT-000304 27 Aug 2026 115, China Stone Construction, The Ring Palm Jumeirah QT-000184 18 Dec 2025 550, Ms Marina	
Substrate primer review	labour only	labour only at defaults; no source	0 no material	history 120 (13 quotes: QT-000250, QT-000304, QT-000184) engine 37.5; history leads	S+A 120/sqm App only 80	QT-000250 02 May 2026 165, White Pearl Interiors QT-000304 27 Aug 2026 115, China Stone Construction, The Ring Palm Jumeirah QT-000184 18 Dec 2025 550, Ms Marina	
Self-levelling compound 3 to 50 mm	Mapei Ultraplan Eco 20 (23 kg) MAPEI, Ultraplan Eco 20 bag 23kg 23 kg at 52/pack, 2.3/unit	1.6 kg/sqm per mm, waste 5% at 2 mm, 1 coat; tds H	7.6/sqm coverage x pack cost x 1.09 + waste, + overhead 12% = our cost 8.5 3 mm: 11.4 5 mm: 19 10 mm: 38.1	history 58 (5 quotes: QT-000298 v1, QT-000298 v3, QT-000300) engine 30; history leads	S+A 58/sqm App only 80 3 mm: 58 5 mm: 58 10 mm: 58	QT-000298 v1 22 Aug 2026 58, Arabian Furniture QT-000298 v3 22 Aug 2026 55, Arabian Furniture QT-000300 22 Aug 2026 50, Tawfeeq Zakarneh	
Cementitious screed 20 to 100 mm review	Mapei Topcem (20 kg binder) MAPEI, Topcem bag 20kg 20 kg at 29/pack, 1.5/unit	2.5 kg binder/sqm per cm (state sand ratio), waste 5% at 2 mm, 1 coat; tds H	38.6/sqm coverage x pack cost x 1.09 + waste, + overhead 12% = our cost 43.5 3 mm: 38.6 5 mm: 38.6 10 mm: 38.6	history 147.5 (8 quotes: QT-000250, QT-000304, QT-000184) engine 40; history leads	S+A 148/sqm App only 80 3 mm: 148 5 mm: 148 10 mm: 148	QT-000250 02 May 2026 165, White Pearl Interiors QT-000304 27 Aug 2026 115, China Stone Construction, The Ring Palm Jumeirah QT-000184 18 Dec 2025 550, Ms Marina	
Flatness check and hand-over	labour only	labour only at defaults; no source	0 no material	history 120 (13 quotes: QT-000250, QT-000304, QT-000184) engine 0; history leads	S+A 120/lump App only 80	QT-000250 02 May 2026 165, White Pearl Interiors QT-000304 27 Aug 2026 115, China Stone Construction, The Ring Palm Jumeirah QT-000184 18 Dec 2025 550, Ms Marina	

Vinyl flooring

Stage	Product and pack	Coverage and defaults	Material per unit	Labour, history vs engine	Rates	Evidence	Contractor correction
SL skim to SR1	labour only	labour only at defaults; no source	0 no material	no past quotes engine 37.5; engine leads	S+A 53/sqm App only 38	engine only	
Moisture barrier	labour only	labour only at defaults; no source	0 no material	no past quotes engine 27; engine leads	S+A 38/sqm App only 27	engine only	
Planks or sheet	labour only	labour only at defaults; no source	0 no material	no past quotes engine 27; engine leads	S+A 38/sqm App only 27	engine only	
Adhesive (glue-down)	labour only	labour only at defaults; no source	0 no material	no past quotes engine 37.5; engine leads	S+A 53/sqm App only 38	engine only	
Thresholds, skirting, scotia	labour only	labour only at defaults; no source	0 no material	no past quotes engine 75; engine leads	S+A 105/lm App only 75	engine only	

Tiling & marble

Stage	Product and pack	Coverage and defaults	Material per unit	Labour, history vs engine	Rates	Evidence	Contractor correction
Substrate flatness verdict SR1/SR2/SR3	labour only	labour only at defaults; no source	0 no material	history 60 (11 quotes: QT-000295, QT-000271, QT-000299) engine 37.5; history leads	S+A 60/sqm App only 38	QT-000295 20 Aug 2026 209, AI Wathba Resorts QT-000271 12 Jun 2026 60, Patio General Trading QT-000299 22 Aug 2026 55- , Jumeirah Bay	
Dry layout and cutting review	labour only	labour only 60x120 tile, 3 mm joint; no source	0 no material	history 60 (11 quotes: QT-000295, QT-000271, QT-000299) engine 65; history leads	S+A 60/sqm App only 65	QT-000295 20 Aug 2026 209, AI Wathba Resorts QT-000271 12 Jun 2026 60, Patio General Trading QT-000299 22 Aug 2026 55- , Jumeirah Bay	
Adhesive (notched + back-butter e 95%) review	Mapei Keraflex Maxi S1 Zero Grey (25 kg) MAPEI, Keraflex Maxi S1 (N) Zero Grey bag 25kg 25 kg at 55/pack, 2.2/unit	6 kg/sqm (by trowel and back-butter), waste 5% 60x120 tile, 3 mm joint; tds H	17.4/sqm coverage x pack cost x 1.09 + waste, + overhead 12% = our cost 19.5	history 160 (6 quotes: QT-000295, QT-000269, QT-000261) engine 65; history leads	S+A 160/sqm App only 65	QT-000295 20 Aug 2026 209, AI Wathba Resorts QT-000269 11 Jun 2026 60- , Rameena Foundation QT-000261 14 May 2026 100, Emi- rates Hills	
Tile or stone supply review	labour only	labour only at defaults; no source	0 no material	history 60 (11 quotes: QT-000295, QT-000271, QT-000299) engine 75; history leads	S+A 60/sqm App only 75	QT-000295 20 Aug 2026 209, AI Wathba Resorts QT-000271 12 Jun 2026 60, Patio General Trading QT-000299 22 Aug 2026 55- , Jumeirah Bay	
Levelling clips and wedges review	labour only	labour only at defaults; no source	0 no material	history 60 (11 quotes: QT-000295, QT-000271, QT-000299) engine 27; history leads	S+A 60/sqm App only 27	QT-000295 20 Aug 2026 209, AI Wathba Resorts QT-000271 12 Jun 2026 60, Patio General Trading QT-000299 22 Aug 2026 55- , Jumeirah Bay	
Sound test	labour only	labour only at defaults; no source	0 no material	history 60 (11 quotes: QT-000295, QT-000271, QT-000299) engine 0; history leads	S+A 60/sqm App only 0	QT-000295 20 Aug 2026 209, AI Wathba Resorts QT-000271 12 Jun 2026 60, Patio General Trading QT-000299 22 Aug 2026 55- , Jumeirah Bay	
Cementitious grout	labour only	labour only at defaults; no source	0 no material	history 60 (11 quotes: QT-000295, QT-000271, QT-000299) engine 37.5; history leads	S+A 60/sqm App only 38	QT-000295 20 Aug 2026 209, AI Wathba Resorts QT-000271 12 Jun 2026 60, Patio General Trading QT-000299 22 Aug 2026 55- , Jumeirah Bay	
Epoxy grout	labour only	labour only at defaults; no source	0 no material	history 57.5 (2 quotes: QT-000271, QT-000272) engine 37.5; history leads	S+A 58/sqm App only 38	QT-000271 12 Jun 2026 60, Patio General Trading QT-000272 12 Jun 2026 55, Mr Livin	
Grout removal (regROUT jobs) review	Mapei Ultracolor Plus (5 kg) MAPEI, Ultracolor Plus 114 ALU bag 5kg (box of 4) 5 kg at 50/pack, 10/unit	1.2 kg/sqm (state tile size and joint), waste 5% 1 coat at TDS coverage; tds H	12.6/sqm coverage x pack cost x 1.09 + waste, + overhead 12% = our cost 14	history 35 (2 quotes: QT-000272, QT-000299) engine 75; history leads	S+A 35/sqm App only 75	QT-000272 12 Jun 2026 15, Mr Livin QT-000299 2026-08-22 55, Jumeirah Bay	
Perimeter and movement joint sealant	labour only	labour only at defaults; no source	0 no material	history 60 (11 quotes: QT-000295, QT-000271, QT-000299) engine 37.5; history leads	S+A 60/lm App only 38	QT-000295 20 Aug 2026 209, AI Wathba Resorts QT-000271 12 Jun 2026 60, Patio General Trading QT-000299 22 Aug 2026 55- , Jumeirah Bay	

Marble pre-seal and im- pregnator review	labour only	labour only at defaults; no source	0 no material	history 60 (11 quotes: QT-000295, QT-000271, QT-000299) engine 75; history leads	S+A 60/sqm App only 75	QT-000295 20 Aug 2026 209, Al Wathba Resorts QT-000271 12 Jun 2026 60, Patio General Trading QT-000299 22 Aug 2026 55- , Jumeirah Bay
--	-------------	---------------------------------------	------------------	--	---------------------------	--

Tiling labour ladder, AED per sqm, application labour

Tile size	30x30	60x60	60x120	80x120	120x120	240x240
Floor	40	40	65	73.3	90	115
Wall	50	50	75	83.3	100	125

Polishing

Stage	Product and pack	Coverage and defaults	Material per unit	Labour, history vs engine	Rates	Evidence	Contractor correction
Grind, hone, polish grit ladder 30 to 3000	labour only	labour only at defaults; no source	0 no material	no past quotes engine 15; engine leads	S+A 21/sqm App only 15	engine only	
Crystallise or seal	labour only	labour only at defaults; no source	0 no material	no past quotes engine 0; engine leads	S+A 0/sqm App only 0	engine only	

Microtopping

Stage	Product and pack	Coverage and defaults	Material per unit	Labour, history vs engine	Rates	Evidence	Contractor correction
Bond test and bonding primer	Kerakoll Universal Wall Primer	62.5 sqm per unit, waste 0% 1 coat at TDS coverage; quote H	2.3/sqm coverage x pack cost x 1.09 + waste, + overhead 12% = our cost 2.5	no past quotes engine 150; engine leads	S+A 213/sqm App only 100	engine only	
Base coat 1 with fibreglass mesh	Mapei Ultratop Loft F (20 kg, base) MAPEI, Ultratop Loft F Natural bag 20kg 20 kg at 353/pack, 17.7/unit	1.5 kg/sqm per mm, waste 5% at 2 mm, 1 coat; tds H	55.6/sqm coverage x pack cost x 1.09 + waste, + overhead 12% = our cost 62.5	no past quotes engine 150; engine leads	S+A 288/sqm App only 100	engine only	
Base coat 2	Mapei Ultratop Loft F (20 kg, base) MAPEI, Ultratop Loft F Natural bag 20kg 20 kg at 353/pack, 17.7/unit	1.5 kg/sqm per mm, waste 5% at 2 mm, 1 coat; tds H	55.6/sqm coverage x pack cost x 1.09 + waste, + overhead 12% = our cost 62.5	no past quotes engine 150; engine leads	S+A 288/sqm App only 100	engine only	
Finish coat (tonal trowel)	Mapei Ultratop Loft W (20 kg, finish) MAPEI, Ultratop Loft W Natural bag 20kg 20 kg at 357/pack, 17.9/unit	1.2 kg/sqm per mm, waste 5% at 2 mm, 1 coat; tds H	45/sqm coverage x pack cost x 1.09 + waste, + overhead 12% = our cost 50.5	no past quotes engine 150; engine leads	S+A 273/sqm App only 100	engine only	
Sand and clean	labour only	labour only at defaults; no source	0 no material	no past quotes engine 150; engine leads	S+A 210/sqm App only 100	engine only	
PU sealer × 2 (matte, satin, gloss)	Mapei Mapectfloor Finish 58 W (A+B) MAPEI, MAPEFLOOR FINISH 58W/A+B NEUTRAL 5.5 KG 5.5 kg at 447/pack, 81.3/unit	0.1 kg/sqm per coat, waste 5% 1 coat at TDS coverage; tds H	17.1/sqm coverage x pack cost x 1.09 + waste, + overhead 12% = our cost 19	no past quotes engine 150; engine leads	S+A 234/sqm App only 100	engine only	

Design concrete

Stage	Product and pack	Coverage and defaults	Material per unit	Labour, history vs engine	Rates	Evidence	Contractor correction
SL screed if needed	labour only	labour only at defaults; no source	0 no material	no past quotes engine 75; engine leads	S+A 105/sqm App only 75	engine only	
Ultratop design pour	Mapei Ultratop Standard (25 kg) MAPEI, Ultratop Standard bag 25kg 25 kg at 207/pack, 8.3/unit	1.7 kg/sqm per mm, waste 5% at 2 mm, 1 coat; tds H	29.6/sqm coverage x pack cost x 1.09 + waste, + overhead 12% = our cost 33	no past quotes engine 0; engine leads	S+A 42/sqm App only 0	engine only	
Stamp or colour-harden	labour only	labour only at defaults; no source	0 no material	no past quotes engine 0; engine leads	S+A 0/sqm App only 0	engine only	
Wet cure under fleece	labour only	labour only at defaults; no source	0 no material	no past quotes engine 0; engine leads	S+A 0/sqm App only 0	engine only	
Grind and hone ladder	labour only	labour only at defaults; no source	0 no material	no past quotes engine 15; engine leads	S+A 21/sqm App only 15	engine only	
Densifier	labour only	labour only at defaults; no source	0 no material	no past quotes engine 0; engine leads	S+A 0/sqm App only 0	engine only	
UV-stable PU sealer × 2	labour only	labour only at defaults; no source	0 no material	no past quotes engine 0; engine leads	S+A 0/sqm App only 0	engine only	

Sealants

Stage	Product and pack	Coverage and defaults	Material per unit	Labour, history vs engine	Rates	Evidence	Contractor correction
Joint geometry survey	labour only	labour only at defaults; no source	0 no material	no past quotes engine 0; engine leads	S+A 0/lm App only 0	engine only	
Backer rod	Closed-cell PE backer rod BACKING ROD 30 MM x 100 M 100 lm at 50/pack, 0.5/unit	100 lm per roll (state dia), waste 5% 1 coat at TDS coverage; tds H	0.5/lm coverage x pack cost x 1.09 + waste, + overhead 12% = our cost 0.5	no past quotes engine 37.5; engine leads	S+A 53/lm App only 38	engine only	
Masking	labour only	labour only at defaults; no source	0 no material	no past quotes engine 37.5; engine leads	S+A 53/lm App only 38	engine only	
Primer (where required)	labour only	labour only at defaults; no source	0 no material	no past quotes engine 37.5; engine leads	S+A 53/lm App only 38	engine only	
Sealant gun-applied and tooled	labour only	labour only at defaults; no source	0 no material	no past quotes engine 37.5; engine leads	S+A 53/lm App only 38	engine only	

Painting

Stage	Product and pack	Coverage and defaults	Material per unit	Labour, history vs engine	Rates	Evidence	Contractor correction
Surface inspection and re-pair	labour only	labour only at defaults; no source	0 no material	no past quotes engine 37.5; engine leads	S+A 53/sqm App only 38	engine only	
Stucco putty 1 to 2 coats, sanded	labour only	labour only at defaults; no source	0 no material	no past quotes engine 37.5; engine leads	S+A 53/sqm App only 38	engine only	
Primer	Dulux Undercoat (18 L) Dulux, DM Dulux Undercoat white 18L 18 L at 162/pack, 9/unit	10 sqm per litre per coat, waste 5% 1 coat at TDS coverage; tds M	94.5/sqm coverage x pack cost x 1.09 + waste, + overhead 12% = our cost 106	no past quotes engine 37.5; engine leads	S+A 185/sqm App only 38	engine only	
Topcoat × 2 with light sand between	Dulux Weathershield Masonry Smooth (5 USG) Dulux, DULUX WEATHERSHIELD MASONRY PAINT SMOOTH White(5USG) 18.93 L at 230/pack, 12.1/unit	9 sqm per litre per coat, waste 5% 1 coat at TDS coverage; tds M	229.4/sqm coverage x pack cost x 1.09 + waste, + overhead 12% = our cost 257	no past quotes engine 37.5; engine leads	S+A 374/sqm App only 38	engine only	
Snag, clean-up, handover	labour only	labour only at defaults; no source	0 no material	no past quotes engine 15; engine leads	S+A 21/lump App only 15	engine only	

Insulation

Stage	Product and pack	Coverage and defaults	Material per unit	Labour, history vs engine	Rates	Evidence	Contractor correction
Spray PU foam closed cell	labour only	labour only at defaults; no source	0 no material	no past quotes engine 0; engine leads	S+A 0/sqm App only 0	engine only	
EPS / XPS / mineral wool boards	labour only	labour only at defaults; no source	0 no material	no past quotes engine 27; engine leads	S+A 38/sqm App only 27	engine only	
Board adhesive and mechanical fixings	XPS / polystyrene board 600x1250x50 mm Polystyrene Insulation Board 600x1250x50MM 0.75 sqm at 19/pack, 25.4/unit	0.7 sqm per board, waste 0% 1 coat at TDS coverage; tds H	27.3/sqm coverage x pack cost x 1.09 + waste, + overhead 12% = our cost 30.5	no past quotes engine 27; engine leads	S+A 76/sqm App only 27	engine only	
Detailing and UV topcoat or cladding	labour only	labour only at defaults; no source	0 no material	no past quotes engine 37.5; engine leads	S+A 53/sqm App only 38	engine only	

Repair

Stage	Product and pack	Coverage and defaults	Material per unit	Labour, history vs engine	Rates	Evidence	Contractor correction
Site survey and NDT (crack width, half-cell, carbonation, cover)	labour only	labour only at defaults; no source	0 no material	no past quotes engine 0; engine leads	S+A 0/lump App only 0	engine only	
Root-cause report and method statement	labour only	labour only at defaults; no source	0 no material	no past quotes engine 0; engine leads	S+A 0/lump App only 0	engine only	
Chip back, clean, treat rebar	labour only	labour only at defaults; no source	0 no material	no past quotes engine 15; engine leads	S+A 21/sqm App only 15	engine only	
Crack injection epoxy or PU	Mapei Eporip (A+B 2 kg, epoxy bonding/crack) MAPEI, EPORIP A+B 2KG 2 kg at 94/pack, 47.1/unit	0.5 kg/sqm or kg per lm crack, waste 5% 1 coat at TDS coverage; tds M	24.7/lm coverage x pack cost x 1.09 + waste, + overhead 12% = our cost 27.5	no past quotes engine 37.5; engine leads	S+A 87/lm App only 38	engine only	
Repair mortar (spalls)	Mapei Mapegrout Thixotropic (25 kg) MAPEI, MAPEGROUT THIXOTOPIC 25KG 25 kg at 23/pack, 0.9/unit	19 kg/sqm per cm, waste 5% at 2 mm, 1 coat; tds H	54.8/sqm coverage x pack cost x 1.09 + waste, + overhead 12% = our cost 61.5	no past quotes engine 37.5; engine leads	S+A 129/sqm App only 38	engine only	
Leak plugging	labour only	labour only at defaults; no source	0 no material	no past quotes engine 37.5; engine leads	S+A 53/nos App only 38	engine only	
CFRP strengthening	labour only	labour only at defaults; no source	0 no material	no past quotes engine 27; engine leads	S+A 38/lm App only 27	engine only	
Surface restoration to match	labour only	labour only at defaults; no source	0 no material	no past quotes engine 37.5; engine leads	S+A 53/sqm App only 38	engine only	

Cross-discipline

Stage	Product and pack	Coverage and defaults	Material per unit	Labour, history vs engine	Rates	Evidence	Contractor correction
Demolition and removal (tile, screed, grout, carpet, wallpaper)	labour only	labour only at defaults; no source	0 no material	no past quotes engine 75; engine leads	S+A 105/sqm App only 75	engine only	
Garbage disposal and protection	labour only	labour only at defaults; no source	0 no material	no past quotes engine 0; engine leads	S+A 0/lump App only 0	engine only	
Scaffolding and access	labour only	labour only at defaults; no source	0 no material	no past quotes engine 0; engine leads	S+A 0/lump App only 0	engine only	
Mobilisation and transport	labour only	labour only at defaults; no source	0 no material	no past quotes engine 0; engine leads	S+A 0/lump App only 0	engine only	
Permits, gate pass, NOC	labour only	labour only at defaults; no source	0 no material	no past quotes engine 0; engine leads	S+A 0/lump App only 0	engine only	
Bought-in finishes (carpet, wallpaper, wooden floor, doors)	labour only	labour only at defaults; no source	0 no material	no past quotes engine 37.5; engine leads	S+A 53/sqm App only 38	engine only	
Packaged small works (per washroom)	labour only	labour only at defaults; no source	0 no material	no past quotes engine 37.5; engine leads	S+A 53/nos App only 38	engine only	

Variables and adjustments

Programme compression, worked example

30 crew-days at 8 hours is 240 crew-hours. A site allowing 6 hours a day on a 6 day week over 15 calendar days gives 77 hours per crew, so 4 crews run at once: congestion adds 30% on the works, mobilisation and tools go times 4, and supervision runs all 15 days.

Occupied building

Productivity factor 0.85: suggested rates on affected lines rise about 18%. Never applied to figures typed by the estimator.

Night work

Prefilled at 10% on the works subtotal, editable per quote.

Upper floor or roof

Multiplies affected line prices by 1.15, editable up to 1.20.

Island logistics, Al Maya reference

Trucks of 4 tons at 2,000 AED each; island sites add a barge at 200 AED per ton. The Al Maya Island 2026 job: 80 tons, 16,000 AED barge. Under 1 ton goes by pickup.

Suggestion coverage

These numbers are engine-only, check hardest here (72 stages)

Waterproofing: Primer | Waterproofing: Reinforcement mesh embed | Waterproofing: Membrane coat 2 | Waterproofing: Detailing (corners, penetrations, upstands) | Waterproofing: Cure and flood test | Waterproofing: Handover IR and documentation | Bitumen WP: Membrane layer 2 offset 50% (where 4+4) | Bitumen WP: Anti-root membrane | Bitumen WP: Geotextile separator 300 gsm | Bitumen WP: Flood test and IR | Epoxy flooring: Moisture test and survey | Epoxy flooring: Crack and joint repair | Epoxy flooring: Primer | Epoxy flooring: Broadcast quartz or flake | Epoxy flooring: Top sealer × 2 coats (UV-stable PU) | Epoxy flooring: PU-cement heavy duty 6 to 9 mm (F&B, cold rooms) | Epoxy flooring: Coving | Epoxy flooring: Sports and TNS coatings | Epoxy flooring: Cure schedule | SL & screed: Edge banding and dams | SL & screed: Substrate primer | SL & screed: Flatness check and handover | Vinyl flooring: SL skim to SR1 | Vinyl flooring: Moisture barrier | Vinyl flooring: Planks or sheet | Vinyl flooring: Adhesive (glue-down) | Vinyl flooring: Thresholds, skirting, scotia | Tiling & marble: Substrate flatness verdict SR1/SR2/SR3 | Tiling & marble: Dry layout and cutting | Tiling & marble: Tile or stone supply | Tiling & marble: Levelling clips and wedges | Tiling & marble: Sound test | Tiling & marble: Perimeter and movement joint sealant | Tiling & marble: Marble pre-seal and impregnator | Polishing: Grind, hone, polish grit ladder 30 to 3000 | Polishing: Crystallise or seal | Microtopping: Bond test and bonding primer | Microtopping: Base coat 2 | Microtopping: Sand and clean | Microtopping: PU sealer × 2 (matte, satin, gloss) | Design concrete: SL screed if needed | Design concrete: Ultratop design pour | Design concrete: Stamp or colour-harden | Design concrete: Wet cure under fleece | Design concrete: Grind and hone ladder | Design concrete: Densifier | Design concrete: UV-stable PU sealer × 2 | Sealants: Joint geometry survey | Sealants: Masking | Sealants: Primer (where required) | Painting: Surface inspection and repair | Painting: Stucco putty 1 to 2 coats, sanded | Painting: Primer | Painting: Topcoat × 2 with light sand between | Painting: Snag, clean-up, handover | Insulation: Spray PU foam closed cell | Insulation: Board adhesive and mechanical fixings | Insulation: Detailing and UV topcoat or cladding | Repair: Site survey and NDT (crack width, half-cell, carbonation, cover) | Repair: Root-cause report and method statement | Repair: Crack injection epoxy or PU | Repair: Repair mortar (spalls) | Repair: Leak plugging | Repair: CFRP strengthening | Repair: Surface restoration to match | Cross-discipline: Demolition and removal (tile, screed, grout, carpet, wallpaper) | Cross-discipline: Garbage disposal and protection | Cross-discipline: Scaffolding and access | Cross-discipline: Mobilisation and transport | Cross-discipline: Permits, gate pass, NOC | Cross-discipline: Bought-in finishes (carpet, wallpaper, wooden floor, doors) | Cross-discipline: Packaged small works (per washroom)

Backed by past quotations (21 stages)

SL & screed: Cementitious screed 20 to 100 mm	10 points	median 125
Waterproofing: Membrane coat 1 (brush or roller)	9 points	median 95
Tiling & marble: Adhesive (notched + back-butter e 95%)	6 points	median 160
SL & screed: Self-levelling compound 3 to 50 mm	5 points	median 58
Bitumen WP: Torch-applied membrane layer 1 (4 mm)	3 points	median 32
Epoxy flooring: Body coat self-levelling 2 to 3 mm	3 points	median 80
Tiling & marble: Epoxy grout	3 points	median 60
Microtopping: Finish coat (tonal trowel)	3 points	median 100
Waterproofing: Site survey and moisture test	2 points	median 28,500
Bitumen WP: Protection board	2 points	median 20
Epoxy flooring: Shotblast or grind and vacuum	2 points	median 15

Tiling & marble: Cementitious grout	2 points	median 1,778
Tiling & marble: Grout removal (regROUT jobs)	2 points	median 35
Microtopping: Base coat 1 with fibreglass mesh	2 points	median 5,605
Waterproofing: Substrate preparation (grind, repair, dust extraction)	1 points	median 30,000
Waterproofing: Protection screed (e 50 mm)	1 points	median 205
Bitumen WP: Bituminous primer	1 points	median 4
Sealants: Backer rod	1 points	median 20
Sealants: Sealant gun-applied and tooled	1 points	median 40
Insulation: EPS / XPS / mineral wool boards	1 points	median 43
Repair: Chip back, clean, treat rebar	1 points	median 150

Confidential, internal only

This page never leaves the company. It is what we pay, not what we charge.

Piece rate, Al Wathba: Paid to crew 50 per sqm with 25 to 30 sqm per day target. Linear work paid 16 per lm; normal linear charge-out 12 to 13 per lm.