

How to quote, discipline by discipline

The recipe book: which lines to add, in order, and which inputs to set. Stage names match the picker exactly.

Every quote, the same eight moves

1. New quote: client, site, site profile (island, hotel, villa: this one choice multiplies all labour)
2. Add the discipline recipe lines from this book, in order, skipping the ones marked optional that do not apply
3. Type the quantity on every line; set the line inputs named in brackets (thickness, tile size, coats, joint size)
4. Check labour: the grey suggestion per line, or type the head contractor total in the gold box and it spreads itself
5. Variables panel: deadline and site hours if the client gave a programme; occupied building; night work
6. Type Your price in the gold column per line; red flag means below our cost, amber means below suggestion
7. Internal strip: check the advance covers material
8. Preview PDF, then Issue. Changes after issue become R2

Every quote ends with the close-out lines

1. Demolition and removal (optional) [sqm] renovation jobs, from Cross-discipline
2. Garbage disposal and protection [lump] type your price, it passes through
3. Scaffolding and access (optional) [lump] height or facade work
4. Mobilisation and transport (optional) [lump] islands and remote sites; the logistics suggestion helps
5. Permits, gate pass, NOC (optional) [lump] hotels, malls, gated areas

Lumps have no engine price: whatever you type passes through. Put the basis in the description (21 days scaffolding, 6 skips) so the next person understands the number.

Waterproofing, liquid or cementitious (wet areas, roofs, tanks)

Mapelastic, Purtop, CM210 and similar brush, roller or spray systems.

1. Demolition and removal (Cross-discipline) (optional) [sqm] renovation only
2. Site survey and moisture test (optional) [lump]
3. Substrate preparation (grind, repair, dust extraction) (optional) [sqm] skip on a new clean slab; its labour auto-absorbs when a coat line is present
4. Primer [sqm]
5. Membrane coat 1 (brush or roller) [sqm] pick the product; set coats, or thickness mm for sprayed Purtop
6. Reinforcement mesh embed (optional) [sqm] systems with mesh, e.g. Mapelastic Smart with Mapenet
7. Membrane coat 2 (optional) [sqm] use either this line or coats 2 on coat 1, never both
8. Detailing (corners, penetrations, upstands) [lm]
9. Cure and flood test [lump] price 0 is fine, always show it
10. Protection screed (e 50 mm)(optional) [sqm] trafficked roofs
11. Handover IR and documentation (optional) [lump]

Then the standard close-out on the last page.

Bitumen torch membrane (roofs, podiums, planters)

Awazel and similar torch-applied SBS rolls.

1. Bituminous primer [sqm]
2. Torch-applied membrane layer 1 (4 mm) [sqm]
3. Membrane layer 2 offset 50% (where 4+4) (optional) [sqm] 4+4 spec only
4. Anti-root membrane (optional) [sqm] planters and green roofs
5. Geotextile separator 300 gsm (optional) [sqm]
6. Protection board [sqm] the calculator warns if a torch membrane has no protection
7. Flood test and IR [lump]

Then the close-out lines and the eight moves from page 1.

Tiling and marble

Floor and wall tile, porcelain, slabs, marble.

1. Substrate flatness verdict SR1/SR2/SR3 (optional) [sqm] SR2/SR3 means add an SL line from SL & screed first
2. Grout removal (regROUT jobs) (optional) [sqm] regROUT only
3. Adhesive (notched + back-butter e 95%)[sqm] this is the install line: set tile size W x H cm (drives adhesive, grout and the labour ladder), tick Wall if wall, tick Material by client if client tiles
4. Tile or stone supply (optional) [sqm] only when we supply the tile, bought-in cost
5. Levelling clips and wedges (optional) [sqm] large format
6. Cementitious grout OR Epoxy grout [sqm] pick one; tile size drives consumption
7. Perimeter and movement joint sealant [lm]
8. Marble pre-seal and impregnator (optional) [sqm] marble only
9. Sound test (optional) [sqm]

Then the close-out lines and the eight moves from page 1.

Epoxy flooring

Warehouses, parking, F&B. Mapefloor and similar.

1. Moisture test and survey (optional) [lump]
2. Shotblast or grind and vacuum [sqm] the calculator nags any resin floor without preparation
3. Crack and joint repair (optional) [lm]
4. Primer [sqm]
5. Body coat self-levelling 2 to 3 mm [sqm] set thickness mm and coats
6. Broadcast quartz or flake (optional) [sqm] anti-slip or decorative
7. Top sealer × 2 coats (UV-stable PU) (optional) [sqm]
8. PU-cement heavy duty 6 to 9 mm (F&B, cold rooms) (optional) [sqm] replaces primer + body coat for heavy duty
9. Coving (optional) [lm] F&B and washdown areas
10. Cure schedule (optional) [sqm] no charge, shows the client the programme is real

Then the close-out lines and the eight moves from page 1.

Self-levelling and screed

Ultraplan, Topcem, Vetotop. Thickness drives material one to one.

1. Edge banding and dams (optional) [lm]
2. Substrate primer [sqm]
3. Self-levelling compound 3 to 50 mm [sqm] set the thickness in mm; 10 mm carries five times the material of 2 mm
4. Cementitious screed 20 to 100 mm (optional) [sqm] use instead of SL for thick builds; thickness in cm
5. Flatness check and handover (optional) [lump]

Then the close-out lines and the eight moves from page 1.

Microtopping and microcement

Ultratop Loft, Kerakoll decorative systems.

1. Bond test and bonding primer [sqm]
2. Base coat 1 with fibreglass mesh [sqm] set base mm and number of base coats on the line
3. Base coat 2 (optional) [sqm] when the system needs a separate second base
4. Finish coat (tonal trowel) [sqm] set finish mm
5. Sand and clean [sqm]
6. PU sealer × 2 (matte, satin, gloss) [sqm] set sealer coats

Then the close-out lines and the eight moves from page 1.

Vinyl flooring

LVT planks and sheet.

1. SL skim to SR1 [sqm]
2. Moisture barrier (optional) [sqm]
3. Adhesive (glue-down) [sqm]
4. Planks or sheet [sqm] supply, bought-in cost
5. Thresholds, skirting, scotia [lm]

Then the close-out lines and the eight moves from page 1.

Design concrete and polishing

Ultratop pours, stamped, polished concrete.

1. SL screed if needed (optional) [sqm]
2. Ultratop design pour [sqm]
3. Stamp or colour-harden (optional) [sqm]
4. Wet cure under fleece [sqm]
5. Grind and hone ladder [sqm]
6. Densifier [sqm]
7. UV-stable PU sealer × 2 [sqm]
8. For polish-only jobs: Grind, hone, polish grit ladder 30 to 3000 + Crystallise or seal (Polishing) [sqm]

Then the close-out lines and the eight moves from page 1.

Sealants and joints

Expansion joints, perimeter joints. Priced per lm.

1. Joint geometry survey (optional) [lm]
2. Backer rod [lm]
3. Masking (optional) [lm]
4. Primer (where required) (optional) [lm]
5. Sealant gun-applied and tooled [lm] set joint width and depth mm on the line

Then the close-out lines and the eight moves from page 1.

Repair and restoration

Concrete repair, injection, strengthening.

1. Site survey and NDT (crack width, half-cell, carbonation, cover) [lump]
2. Root-cause report and method statement (optional) [lump]
3. Chip back, clean, treat rebar [sqm]
4. Crack injection epoxy or PU (optional) [lm]
5. Repair mortar (spalls) [sqm]
6. Leak plugging (optional) [nos]
7. CFRP strengthening (optional) [lm] engineer specified
8. Surface restoration to match [sqm]

Then the close-out lines and the eight moves from page 1.

Painting

Internal decorative painting.

1. Surface inspection and repair [sqm]
2. Stucco putty 1 to 2 coats, sanded (optional) [sqm]
3. Primer [sqm]
4. Topcoat × 2 with light sand between [sqm] set coats
5. Snag, clean-up, handover (optional) [lump]

Then the close-out lines and the eight moves from page 1.

Insulation

Roofs and walls.

1. Spray PU foam closed cell OR EPS / XPS / mineral wool boards [sqm] pick the system
2. Board adhesive and mechanical fixings (optional) [sqm] board systems
3. Detailing and UV topcoat or cladding (optional) [sqm]

Then the close-out lines and the eight moves from page 1.